MICROCOPY RESOLUTION TEST CHART

NATIONAL BUREAU OF STANDARDS 1963 A

RESTORATION OF PYRITIC SOILS AND THE QUANTIFICATION OF EROSION CONTROL

by

Charles R. Lee, John G. Skogerboe

Environmental Laboratory

DEPARTMENT OF THE ARMY
Waterways Experiment Station, Corps of Engineers
PO Box 631
Vicksburg, Mississippi 39180-0631

October 1984
Final Report

DTIC
ELECTE
DEC 3 1 1984
S D

D

AD-A148 946

DTIC FILE COPY

84 12 18 1 01

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER Miscellaneous Paper EL-84-7	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) RESTORATION OF PYRITIC SOILS AND THE QUANTIFI- CATION OF EROSION CONTROL		5. TYPE OF REPORT & PERIOD COVERED Final report
		6. PERFORMING ORG. REPORT NUMBER
7. AUTHOR(s) Charles R. Lee John G. Skogerboe		8. CONTRACT OR GRANT NUMBER(s)
9. PERFORMING ORGANIZATION NAME AND ADDRESS US Army Engineer Waterways Experiment Station Environmental Laboratory PO Box 631, Vicksburg, Mississippi 39180-0631		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS Environmental Impact Research Program
11. CONTROLLING OFFICE NAME AND ADDRESS DEPARTMENT OF THE ARMY US Army Corps of Engineers Washington, DC 20314-1000		12. REPORT DATE October 1984
		13. NUMBER OF PAGES 20
14. MONITORING AGENCY NAME & ADDRESS(if different from Controlling Office)		15. SECURITY CLASS. (of this report) Unclassified
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE

16. DISTRIBUTION STATEMENT (of this Report)

Approved for public release; distribution unlimited.

17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)

18. SUPPLEMENTARY NOTES

Available from National Technical Information Service, 5285 Port Royal Road, Springfield, Virgina 22161.

19. KEY WORDS (Continue on reverse side if necessary and identify by block number)

Soil conservation (LC)
Soils--iron content (LC)
Soil amendments (LC)
Acid soils (LC)

20. ABSTRACT (Continue on reverse side if necessary and identify by block number)

Two papers published in the proceedings of the 1983 Symposium on Surface Mining, Hydrology, Sedimentology and Reclamation sponsored by the University of Kentucky are presented. The papers are entitled "Vegetative Restoration of Pyritic Soils" and "Quantification of Erosion Control and Runoff Water Quality from Pyritic Soil Restoration Demonstration Plots." The first paper presents the results of a pyritic soil restoration project designed to demonstrate

(Continued)

DD FORM 1473 EDITION OF 1 NOV 65 IS OBSOLETE
1 JAN 73

20. ABSTRACT (Continued).

restoration methods described in Instruction Report EL-84-1, "Restoration of Problem Soil Materials at CE Construction Sites," developed at the U. S. Army Engineer Waterways Experiment Station (WES). Restoration methods include the use of soil amendments and adapted species for long-term establishment of grasses, legumes, and woody species for erosion control.

The second paper describes a technique employing the WES rainfall simulator to quantify the effectiveness of restoration techniques for controlling erosion and runoff water quality. A laboratory rainfall simulator lysimeter system was developed for estimating soil loss from disturbed soils. These data were then verified in the field using the mobile WES rainfall simulator on the demonstration plots.

Accession For

NTIS GRA&I	☒
DTIC TAB	☐
Unannounced	☐
Justification	

By
Distribution/

Availability Codes	
Dist	Avail and/or Special
A	

DTIC
COPY
INSPECTED
4

PREFACE

These papers were presented at the 1983 Symposium on Surface Mining, Hydrology, Sedimentology, and Reclamation held in Lexington, Kentucky, on 27 November-2 December 1983 and were published in the symposium proceedings by the University of Kentucky.

These papers presented the results of a pyritic soil restoration demonstration project funded by the Department of the Army under the Environmental Impact Research Program sponsored by the Office, Chief of Engineers (OCE).

The demonstration was conducted at the Tennessee-Tombigbee Waterway, Divide Section, Paden, Mississippi, and at the U. S. Army Engineer Waterways Experiment Station (WES), Vicksburg, Mississippi. The work was conducted by Dr. C. R. Lee, Mr. J. G. Skogerboe, and Mr. D. L. Brandon of the Environmental Laboratory (EL), WES; Mr. J. W. Linkinhoker and Mr. R. B. Sneed of the U. S. Army Engineer District, Nashville; and Mr. S. P. Faulkner of the Mississippi State University Soil Testing Laboratory. Technical assistance was provided by Mr. R. A. Price and LT K. T. Eskew, EL. These papers were prepared under the general supervision of Dr. John Harrison, Chief, EL, and under the direct supervision of Mr. D. L. Robey, Chief, Ecosystems Research and Simulation Division, EL. Dr. R. T. Saucier, EL, was Program Manager, and Dr. J. Bushman, OCE, was Technical Monitor.

Commander and Director of WES during the preparation and publication of these papers was COL Tilford C. Creel, CE. Technical Director was Mr. F. R. Brown.

This report should be cited as follows:

Lee, C. R., and Skogerboe, J. G. 1984. "Restoration of Pyritic Soils and the Quantification of Erosion Control," Miscellaneous Paper EL-84-7, U. S. Army Engineer Waterways Experiment Station, CE, Vicksburg, Miss.

CONTENTS

RESTORATION OF PYRITIC SOILS AND THE QUANTIFICATION OF EROSION CONTROL

PART I: VEGETATION RESTORATION OF PYRITIC SOILS

Introduction

1. The U. S. Army Corps of Engineers (CE) is the largest water resource developer in the Nation. As such the CE disturbs enormous quantities of soil materials at its numerous construction sites. Consequently, soil erosion control is a major concern at most CE project sites. In order to provide state-of-the-art technology for effective soil erosion control at CE construction sites, a comprehensive review and compilation of all existing information on vegetative restoration techniques for problem soils was conducted. From existing information, the most effective restoration techniques were formulated and an instruction report was prepared.[1] These techniques included soil amendments that have been shown to improve soil fertility and structure in combination with tolerant plant species adapted to specific problem soils. Since the restoration techniques were formulated from information from a wide variety of unrelated sources, a need arose to demonstrate the effectiveness of the techniques at specific CE project sites. This paper presents the results of vegetative restoration of pyritic soil material at one such CE project site in northeast Mississippi.

Methods

2. During project construction, excavated soil material was placed in disposal sites adjacent to the project. Two disposal sites were selected near Paden, Mississippi, that were characterized as being extremely acid (pH 2.9), droughty, and severely compacted. Each disposal site was divided into 24 plots measuring 15.2 m × 15.2 m with 12 treatment combinations replicated twice. The treatment combinations consisted of 4 soil amendments and 3 plant species (Table 1).

Soil incorporation

3. Soil amendments were incorporated in the following manner. One half of the fine and coarse lime was spread over the plots. A 9.4-cm disk harrow

Table 1. Soil Amendments and Plant
Species Tested.

Soil Amendments

Lime

   100 mt/ha fine agricultural limestone

   100 mt/ha coarse limestone (passing a
    1.9-cm screen)

Lime and manure

   Lime as above

   79.6 mt/ha chicken manure (35% moist)

Lime and phosphate

   Lime as above

   6.5 mt/ha rock phosphate (passing a
   No. 10 sieve)

Lime, manure, and phosphate

   Lime as above

   Chicken manure as above

   Rock phosphate as above

Plant Species	Seeding Rate
Weeping lovegrass	11 kg/ha
Pensacola bahiagrass	38.1 kg/ha
Interstate Sericea lespedeza	33.6 kg/ha

was used in two passes to mix the lime within a 15-cm soil depth. A four-bladed turnplow was then used to invert the top 30- to 45-cm soil depth. The remaining lime was spread and disked twice as before. The turnplow was used again to invert the soil. One half of the manure and phosphate was then applied to appropriate plots. All plots were then disked and turnplowed as before. The remaining half of each material was applied, followed by disking and turnplowing. A five-shank parabolic subsoiler was used before and after the application and incorporation of soil amendments. The plots were then fertilized with 149 kg/ha of ammonium nitrate and 258 kg/ha of 0-17-34, disked with a 7.9-cm disk harrow, cultipacked, seeded, cultipacked, mulched with 6.7 mt/ha of straw, and crimped along the contour.

4

4. An additional set of 16 plots were established on one disposal site. These plots were designed to evaluate subsoiling, fine limestone, coarse limestone, and chicken manure applications incorporated only with a 9.4-cm disk harrow. The turnplow was not used on these plots. Plots were fertilized and seeded as above with only weeping lovegrass at the rate shown in Table 1. All treatment combinations were replicated twice.

5. Kentucky-31 tall fescue was seeded in the alleyways between plots and in a 3.0-m-wide border around the entire plot areas. Annual rye grass was seeded at a rate of 10 kg/ha over the entire plot areas for a quick temporary cover.

6. After one year, each plot was divided in half and seedlings of ten woody plant species were planted in rows of eight seedlings each. Rows were spaced 1.2 m apart. Seedlings were spaced 1.0 m apart within the row. Survival of each seedling was observed 4 months after planting.

Sampling

7. Soil core samples to 90-cm depth were collected at 15-cm increments from each plot prior to soil amendment application and again 9 months after incorporation. Soil samples were sent to the State Soil Test Laboratory at Mississippi State University for soil analyses. Soil samples were analyzed for pH,[2] % organic matter,[3] conductivity,[4] exchangeable phosphorus,[2] exchangeable potassium,[2] exchangeable calcium,[4] exchangeable magnesium,[4] cation exchange capacity,[4] and texture.[5]

8. Vegetative biomass yield data were collected at the maximum vegetative growth stage of the three plant species tested. Each plot was sampled twice randomly using a 9.4-cm square by harvesting all of the aboveground vegetation within the square. Plant samples were oven dried to constant weights at 70° C and reported.

Results and Discussion

Soil analyses

9. The texture of the soil in the disposal sites was predominantly a fine sandy loam with a cation exchange capacity of 28 milliequivalents/100 g. Generally there were few significant differences across plots for most parameters before soil amendment applications (Table 2). Soil pH before soil

Table 2. Soil Analyses Before and After Soil Amendment
Application.

| Parameter | Sample | Soil Amendment | | | |
		Lime	Lime, Phosphate	Lime, Manure	Lime, Manure, Phosphate
pH	Before	3.04 aA*	3.22 aA	2.82 aA	2.87 aA
	After**	6.26 aB	5.86 aB	6.14 aB	6.17 aB
Organic matter, %	Before	0.56 aA	0.66 aA	0.54 aA	0.52.aA
	After	0.69 aA	0.69 aA	0.92 aB	0.99 aB
Conductivity, mmhos/cm	Before	1.63 abA	1.44 bA	1.95 aA	2.02 aA
	After	1.83 aA	1.88 aA	2.06 aA	2.12 aA
Phosphorus, ppm	Before	39 aA	26 aA	53 aA	32 aA
	After	14 bA	20 bA	54 aA	62 aB
Potassium, ppm	Before	28 bA	60 aA	26 bA	23 bA
	After	52 bB	53 bA	178 aB	199 aB
Calcium, ppm	Before	1204 aA	1478 aA	1450 aA	12,7 aA
	After	3814 aB	3573 aB	3825 aB	3858 aB
Magnesium, ppm	Before	196 aA	240 aA	240 aA	214 aA
	After	228 bA	240 bA	254 abA	276 aB

 * Means followed by the same small letter across a row are not signifi-
cantly different at P = 0.05 . Means followed by the same capital letter
within a column indicate no significant difference before and after soil
amendment application at P = 0.05 .
** Soil samples collected 9 months after application.

amendment applications ranged from 2.82 to 3.22 (Table 2). Nine months after
application and incorporation of soil amendments, soil pH values were raised
to a range of 5.86 to 6.26. Lime applications increased soil pH and exchange-
able calcium as expected. Manure applications increased percent organic mat-
ter and exchangeable potassium (Table 2). Rock phosphate applications showed
limited increase in exchangeable phosphorus and only in combination with
manure. Rock phosphate is slowly soluble and would be expected to have
limited influence on exchangeable phosphorus initially.

Vegetation responses

10. Grass and legume. Chicken manure increased the yield of all plant
species to some extent (Table 3). Bahiagrass appeared to respond greater to

6

Table 3. Effect of Soil Amendments on Yield (kg/ha) of Bahiagrass,
Weeping Lovegrass, and Sericea Lespedeza.

Soil Amendment	Plant Species		
	Bahiagrass	Weeping Lovegrass	Sericea Lespedeza
Lime	1636 aA*	2666 abAB	2957 bA
Lime, phosphate	2033 aA	1954 aA	3379 bA
Lime, manure	4963 aB	4382 bB	3828 bAB
Lime, manure, phosphate	4989 aB	3458 bAB	4831 aB

* Means followed by the same small letter across a row are not significantly
different at P = 0.05 . Means followed by the same capital letter within
a column are not significantly different at P = 0.05 .

manure applications than the other two species. Sericea lespedeza appeared to
show more response to rock phosphate applications than the other two species
(Table 3). Manure applications resulted in enormous growth of weed species
such as Johnson grass and lambsquarter throughout the plots during the initial
growth season. The persistence of the weed population will be monitored.

11. Woody species. Best survival of woody plant species was observed for
autumn olive, white ash, black locust, bristly locust, and indigobush
(Table 4). Poorest survival was observed for river birch and Virginia pine.
The Virginia pine seedlings appeared to be extremely dry around their roots
when seedling bundles were opened at planting. Most of the other species had
moist roots when unpacked.

12. Survival of seedlings planted in an untreated control area having a
soil pH of 2.9 was autumn olive, 31%; white ash, 19%, black locust, 50%;
bristly locust, 44%; indigobush, 44%; bur oak, 31%; black alder, 62%; northern
red oak, 44%; river birch, 6%, and Virginia pine, 0%.

Soil depth incorporation

13. Grass species. Mixing soil amendments to a depth of 45 cm increased
the yield of weeping lovegrass for both soil amendments (Table 5). The
greater depth of improved growth media appeared to significantly enhance plant
growth and yield. This effect should be even more pronounced during droughty
periods of limited soil moisture.

Table 4. Effect of Soil Amendments on the Percent Survival of Woody Plant Species.

| Plant Species | Soil Amendment | | | | Species Means |
	Lime	Lime, Phosphate	Lime, Manure	Lime, Manure, Phosphate	
Autumn olive	100 aA*	98 aA	92 bAB	100 aA	97 A
White ash	100 aA	90 aA	100 aA	100 aA	97 A
Black locust	98 aA	98 aA	98 aA	100 aA	98 A
Bristly locust	96 abA	98 aA	83 bAB	96 abA	93 A
Indigobush	94 aA	98 aA	92 aAB	96 aA	95 A
Bur oak	83 aA	85 aA	77 aB	81 aAB	82 B
Black alder	79 aAB	62 aB	75 aB	83 aAB	75 B
Northern red oak	94 aA	77 abAB	54 bc	67 abB	73 B
River birch	62 aB	21 bC	29 abD	42 abC	38 C
Virginia pine	35 aC	31 aC	38 aCD	29 aC	33 C
Soil amendment means	84 a	76 b	74 b	79 ab	

* Means followed by the same small letter across a row are not significantly different at P = 0.05 . Means followed by the same capital letter within a column are not significantly different at P = 0.05 .

Table 5. Effect of Depth of Incorporation on Vegetative Biomass Yield (kg/ha) of Weeping Lovegrass for Two Soil Amendments.

| Incorporation Depth | Soil Amendment | |
	Lime	Lime, Manure
0-15 cm	2561 bA*	4594 aA
0-45 cm	4224 bB	6626 aB

* Means followed by different small letters across a row are significantly different at P = 0.05 . Means followed by different capital letters under each soil amendment are significantly different at P = 0.10 .

PART II: QUANTIFICATION OF EROSION CONTROL AND RUNOFF WATER QUALITY
FROM PYRITIC SOIL RESTORATION DEMONSTRATION PLOTS

Introduction

16. Long-term soil erosion control measures for construction sites have emphasized the establishment of vegetation as quickly as possible following construction. This has often been difficult when problem soils were present such as those containing large quantities of pyrite. Much of the soil at these sites has been eroded away before adequate vegetation could be established.

17. An instruction report has been prepared from existing literature by the U. S. Army Engineer Waterways Experiment Station (WES) and provides effective long-term restoration techniques for problem soils encountered at Corps of Engineers project sites. Some of these techniques have been demonstrated at Corps sites, such as on the Tennessee-Tombigbee Waterway, Divide Section. This site was characterized as pyritic, extremely acid (pH 2.5-3.5), droughty, and severely compacted. Erosion problems had developed when previous attempts to vegetate the area failed using standard agronomic techniques.

18. While the addition of more soil amendments will be more expensive initially, the added cost will be compensated in the long term by increased vegetation yields and erosion control. The use of organic matter, particularly organic wastes, may create runoff water quality problems, however. A monitoring program was conducted to quantify the effectiveness of these restoration techniques in establishing vegetation[6] and controlling erosion and runoff water quality.

19. Using the WES rainfall simulator, data were collected to determine the relative effectiveness of different soil amendments and plant species in controlling erosion. Simulated storm events were applied to laboratory lysimeters planted with Kentucky-31 tall fescue and weeping lovegrass. Runoff data were collected to determine hydrographs and suspended solids (SS) concentrations and loads at different biomasses for each species.

20. Field rainfall simulations were conducted to provide field verification of laboratory lysimeter data as well as to evaluate the effects of different soil amendments on runoff water quality. This paper presents the results of this study.

10

Rainfall simulator

21. The WES rainfall simulator was used for erosion and runoff water quality tests on lysimeter and field plots. It is a rotating disk type rainfall simulator designed to accurately simulate the kinetic energy of natural rainfall at impact on the soil surfaces.[7] It is capable of delivering 0 to 7.4 cm/hr over an area 4.57 m × 1.22 m (5.57 m^2).[8] The simulator has proven very effective in erosion prediction[9] and runoff water quality[10] from Corps project sites.

Lysimeter tests

22. Soil was collected at the field site, transported back to the WES, and placed in lysimeters, 4.57 m × 1.22 m (5.57 m^2), Figure 1. Lime and fertilizer were applied and incorporated to simulate the application and incorporation of soil amendments in the field plots. A different species of vegetation was planted in each lysimeter: Kentucky-31 tall fescue and weeping lovegrass.

Figure 1. The laboratory rainfall
simulator - lysimeter
system.

23. Rainfall simulations were conducted at 5.3 cm/hr for 1 hr when vegetation attained a sufficient biomass. After each simulation, the vegetation was cut to a lower height, oven dried, and weighed to determine the biomass. The first series of rainfall simulations conducted on Kentucky-31 tall fescue evaluated different intensities, slopes (2 to 15 percent), and soil moistures. These variables proved to have little statistically significant effects on SS concentrations compared to biomass effects.[9] Later simulations, using weeping lovegrass, were conducted at 5.3 cm/hr on a 5 percent slope. Runoff from the lysimeter flowed into a collection box and through a pipe where runoff rates were measured and samples collected. Suspended solids were determined according to Standard Methods.[11] The data were used to calculate the hydrographs and SS concentrations and loads for each species and biomass.

Field simulations

24. Simulator test plots were established at the Tennessee-Tombigbee Waterway, Divide Section, on 8 field demonstration plots planted with weeping lovegrass and having 4 combinations of soil amendments (Figure 2). An additional simulation plot was constructed on an area with no soil amendments and on 2 limed plots planted with Sericea lespedeza and Pensacola bahiagrass. Areas, 4.57 m × 1.22 m (5.57 m^2), were marked on the field plots and galvanized steel sides hammered into the soil, 10 to 15 cm deep. A runoff collection box was placed at the bottom of each plot where a pump was used to collect runoff and measure runoff rates. The slopes of each plot were measured using a transit and averaged about 5 percent, the same as the lysimeter. The rainfall simulator was moved from plot to plot using a specialized tractor-trailer rig (Figure 3).

25. Two rainfall simulations were conducted on each plot at 5.3 cm/hr for 1 hr each. The second simulation started about 4 hr after the first run, so each plot was subjected to a rainfall event at the same antecedent soil moisture. Runoff rates were measured and samples collected as in the lysimeter tests. Samples were analyzed for SS, pH, ammonium nitrogen (NH_4-N), nitrate nitrogen (NO_3-N), total Kjeldahl nitrogen (TKN), total phosphate (TP), and potassium. Biomass samples were collected from each simulation plot by harvesting all the vegetation in three 1.22-m^2 areas within the plot. Biomass samples were oven dried and weighed.

Figure 2. A field rainfall simulator
plot with the rainfall
simulator.

Figure 3. The tractor-trailer rig used for transporting and operating
the rainfall simulator in the field.

Results and Discussion

Lysimeter rainfall simulations

26. The lysimeter rainfall simulations were designed to predict erosion from field plots and reduce the time and cost of field work. Regression analysis of the log of SS concentrations and loads revealed high correlations for both Kentucky-31 tall fescue and weeping lovegrass (Table 6). There were significant differences in erosion control between species (Figures 4 and 5). The best erosion control was obtained from fescue. Weeping lovegrass erosion control was inferior to fescue, probably because of its longer, thinner leaves which intercepted less rainfall.

Table 6. Suspended Solids Versus Biomass Relationships
from the Laboratory Rainfall Simulator –
Lysimeter System.

| Species	SS Concentrations			SS Loads		
	Slope	Intercept	R^2	Slope	Intercept	R^2
Weeping lovegrass	-2.36×10^{-4}	562	0.96	-2.86×10^{-4}	2371	0.98
KY-31 tall fescue	-5.83×10^{-4}	617	0.96	-6.15×10^{-4}	380	0.94

Figure 4. Suspended solids concentrations from
lysimeter simulations.

Figure 5. Suspended solids loads from lysimeter
simulations.

Lysimeter versus field

27. Even though SS concentrations and loads versus biomass correlated
very well in the lysimeter data, some field calibration was necessary to ver-
ify the lysimeter relationships. Different soil amendments produced wide
ranges in biomass, similar to the range of biomasses obtained in the labora-
tory lysimeters. Linear regression analysis was applied to both the lysimeter
data and the field data. Comparison of SS concentrations versus biomass love-
grass data from the field and lysimeter showed greater variability in field
data (Table 7); however, the regression line was almost identical to the
lysimeter data (Figure 6). Slopes and intercepts for the field and lysimeter
data were identical. Analysis of SS loads versus biomass, however, shows the
lysimeter and field data having the same slope but different intercepts
(Table 7). The relationship developed from lysimeter data accurately esti-
mated SS concentrations but overestimated SS loads from field plots (Fig-
ure 7). The overestimation was primarily caused by reductions in runoff vol-
umes on field plots caused by surface storage of runoff. Lysimeter soil
surfaces were easily controlled and had few depressions and furrows. Field
plots were contour plowed using heavy tractors and plows, creating many small
depressions and furrows to retain and store surface runoff. On smoother field
plots, runoff volumes and SS loads would approach or equal lysimeter estimates
but would never exceed them. The lysimeter, therefore, did predict the

15

maximum potential SS loads possible from field plots. To compensate for this effect a surface storage coefficient of 0.5 was calculated from field and lysimeter lovegrass data.

Table 7. Suspended Solids Versus Biomass Relationships of Weeping Lovegrass from Field and Laboratory Lysimeter.

| Site	SS Concentrations			SS Loads		
	Slope	Intercept	R^2	Slope	Intercept	R^2
Lysimeter	-2.36×10^{-4}	562	0.96	-2.86×10^{-4}	372	0.98
Field	-2.47×10^{-4}	562	0.83	-3.04×10^{-4}	182	0.75

Figure 6. Suspended solids concentrations from field versus lysimeter simulations.

Erosion control
effectiveness of field plots

28. Vegetation biomass yields were determined for the first-year growth on pyritic soil restoration plots (Table 8). Using the average yield for each soil amendment and plant species, soil loss for each treatment was calculated from prediction equations developed with laboratory lysimeter data (Table 8). The addition of chicken manure to field plots produced higher yields of weeping lovegrass, enough to reduce soil loss by more than 50 percent over nonmanure plots.

Figure 7. Suspended solids loads from field
versus lysimeter simulations.

Table 8. Soil Loss from Field Plots Calculated from
Laboratory Lysimeter Relationships and
Field Vegetation Biomass Yields.

Treatment	Yield kg/ha	SS Concentrations mg/ℓ	SS Loads kg/ha
Lime	2666	132	31
Lime, phosphate	1954	194	50
Lime, manure	4382	52	10
Lime, manure, phosphate	3458	86	19

Runoff water quality

29. The use of organic matter as a soil amendment can significantly
increase vegetation biomass yields and erosion control. Some types of organic
materials produce undesirable contaminants in runoff such as excessive nutri-
ents, which could cause eutrophication of waterways. Runoff samples from
field rainfall simulations were analyzed for nutrients to determine undesir-
able effects from chicken manure and rock phosphate. Chicken manure applica-
tions tended to increase runoff concentrations of TKN, TP, and K. Large
variations in NH_4-N and NO_3-N data resulted in very little statistical differ-
ences at P = 0.05 among soil amendments (Table 9).

17

Table 9. Nutrient Concentrations in Runoff Water from
Field Restoration Plots.

| Treatment | Runoff Concentrations, mg/ℓ | | | | |
	NH_4-N	NO_3-N	TKN	TP	K*
Lime	0.12 ab**	0.05 a	0.88 bc	0.17 b	4.68 bc
Lime, phosphate	0.07 b	0.04 a	0.65 c	0.25 b	2.68 c
Lime, manure	0.54 a	0.38 a	1.60 a	0.44 a	11.82 a
Lime, manure, phosphate	0.28 ab	0.13 a	1.47 ab	0.48 a	10.67 ab

* K concentrations are in μg/ℓ.
** Means under a column followed by different letters are significantly
   different at P = 0.05 using Duncan's Multiple Range Test.

30. Runoff water quality loads were calculated from estimated runoff
volumes and concentrations. Runoff volumes were calculated for each soil
treatment using a regression equation from field simulation data:

$$\text{Runoff Volume} = 10^{-0.000058(\text{Biomass}) + 2.26}$$

$$R^2 = 0.31$$

Nutrient loads from manure plots were elevated over nonmanure plots
(Table 10).

Table 10. Vegetation Yield, Runoff Volume, and Nutrient Loads
in Runoff Water from Field Restoration Plots.

| Treatment | Vegetation Yield kg/ha | Runoff Volume ℓ/ha | Loads, g/ha | | | | |
			NH_4-N	NO_3-N	TKN	TP	K
Lime	2666	227,800	27.3	11.4	200.5	38.7	1.07
Lime, phosphate	1954	251,100	17.6	10.0	163.2	62.8	0.67
Lime, manure	4382	183,000	98.8	69.5	292.8	80.5	2.16
Lime, manure, phosphate	3458	206,300	57.8	26.8	303.3	99.0	2.20

Conclusions

31. The use of more extensive soil amendments will increase restoration costs initially. This can often be compensated by an increase in vegetation yield and erosion control. The WES rainfall simulator determined the effectiveness of restoration techniques recommended by an instruction report being developed at WES. Organic matter such as chicken manure can produce higher yields and decreased soil loss by 50 percent or more. Higher nutrient concentrations and loads were observed in runoff water from chicken manure amended plots at the Tennessee-Tombigbee Waterway field plots during the first year following application.

32. Yearly vegetation yield data will continue to be collected from field plots for different plant species and soil amendments. Additional runoff data will be collected for Pensacola bahiagrass and Sericea lespedeza using a lysimeter. Long-term erosion control data will, thus, be collected for all restoration plots on the Tennessee-Tombigbee Waterway, Divide Section.

REFERENCES

1. C. R. Lee, et al., "Restoration of Problem Soil Materials at Corps of Engineers Construction Sites," Instruction Report EL-84-1, U. S. Army Engineer Waterways Experiment Station, CE, Vicksburg, Miss., July 1984.

2. W. E. Sabbe, et al., Eds. "Procedures Used by State Soil Testing Laboratories in the Southern Region of the United States," Bulletin No. 191, Southern Cooperative Series, Alabama State Experiment Station, Aurburn, Ala., July 1974.

3. D. C. DeBolt, "A High Sample Volume Procedure for the Colorimetric Determination of Soil Organic Matter," Communications in Soil Science and Plant Analysis, 5:131-137, 1974.

'. C. A. Black, Ed. "Methods of Soil Analysis, Part 2: Chemical and Microbiological Properties," Monograph No. 9, American Society of Agronomy, Madison, Wis. 1965.

5. W. H. Patrick, Jr., "Modification of Method of Particle Size Analysis," Soil Science Society of America Proceedings, 22:366-367, 1958.

6. C. R. Lee, and J. G. Skogerboe, "Vegetative Restoration of Pyritic Soils," Proceedings, 1983 Symposium on Surface Mining, Hydrology, Sedimentology, and Reclamation, Lexington, Ky, University of Kentucky, Dec. 1983.

7. J. Morin, C. B. Cluff, and W. R. Powers. "Realistic Rainfall Simulation for Field Investigation," Presented at 51st Meeting of American Geophysical Union in Washington, D. C., p 22, 1970.

8. H. E. Westerdahl, and J. G. Skogerboe, "Realistic Rainfall and Watershed Response Simulations for Assessing Water Quality Impacts of Land Use Management," Proceedings of the International Symposium on Rainfall Runoff Modeling, Mississippi State University, Mississippi, Water Resources Publications, pp 87-104, May 1981.

9. C. R. Lee, and J. G. Skogerboe, "Quantification of Soil Erosion Control by Vegetation on Problem Soils," Proceedings, International Conference on Soil Erosion and Conservation, Honolulu, Hawaii, Soil Conservation Society of America, Jan. 1983.

10. C. R. Lee, and J. G. Skogerboe, "Prediction of Surface Runoff Water Quality from an Upland Dredged Material Disposal Site," Proceedings, International Conference on Heavy Metals in the Environment, Heidelberg, Germany, Sept. 1983.

11. Standard Methods for the Evaluation of Water and Wastewater, 15th Ed., American Public Health Association, 1980.

END

FILMED

2-85

DTIC